# BRUHATH BENGALURU MAHANAGARA PALIKE
## Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

## APPROVED TENDER SCHEDULE –'B'

Name of Work:-:IMPROVEMENTS TO ROADS AND DRAINS AT KOTEBHEEDHI ROAD IN WARD NO.02 OF YELAHANKA SUB-DIVISION

| Sl | Description | Unit | Approved Qty | Approved Rate Technical Manager (West) KRIDL, BBMP, | |
|---|---|---|---|---|---|
| | | | | Rate | Rate in Words |
| 1 | **Removing B.S. slab** of Drain and stacking.(P No.25 / I N 5.32) | Sqm | 411.00 | 65.72 | Rupees sixty five and paise seventy two only |
| 2 | KSRRB 300 - Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH Chapter 3 (P.142/I.19.1 ) | Cum | 223.68 | 86.92 | Rupees eighty six and paise ninety two only |
| 3 | KSRB 2-1.1 : Earthwork in surface excavation in **ordinary soil** for **levelling and lowering** the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications. specification. No. KBS 2.1 (a) / 2.3.1 (P.5/I.2.1 ) | Cum | 305.03 | 166.42 | Rupees one hundred sixty six and paise forty two only |
| 4 | KSRRB M100-1 Loading and Unloading of Stone Boulder / Stone aggregate /sand/kaner/ Moorum KSRRB M100-1 Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications MORTH - 100/ Chapter 1 (Page No.133/ Item No 17.1) | Cum | 528.71 | 100.00 | Rupees one hundred only |
| 5 | **Refixing stone slabs** of drains and pointing in C.M.(1:3)(P.No.25/I.No.5.33) | Sqm | 369 90 | 80.56 | Rupees eighty and paise fifty six only |
| 6 | Providing and fixing **RCC precast Slabs of 0.10 m thick of CC 1:2:4 with 20 mm** and down size graded granite metal , machine mixed , including cost of all material , labour , HOM of Machinery , curing complete | Sqm | 41.10 | 2100.00 | Rupees two thousand one hundred only |

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

| | Description | Unit | Approved Qty | Approved Rate Technical Manager (West) KRIDL, BBMP, | |
|---|---|---|---|---|---|
| | | | | Rate | Rate in Words |
| 7 | KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.Specification No.KBS 4.1, 4.2 (P.12/I.4.3) | Cum | 188.57 | 5159.02 | Rupees five thousand one hundred fifty nine and paise two only |
| 8 | Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) M20 for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, for raft foundation, column footing, main and secondary beams with all lead and lifts etc.,complete (exclusive of cost of steel and fabrication charges.) Page No.18 / Item No. 4.48) | Cum | 147.16 | 6231.74 | Rupees six thousand two hundred thirty one and paise seventy four only |
| 9 | Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratiry, Power Floater, blade and disc etc., with all lead and lift (P.177/ I.22.7) | Sqm | 1257.10 | 95.40 | Rupees ninety five and paise forty only |
| 10 | Providing Groove cutting for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine generator and HOM of machinery including cost of blade, coolant etc., including cleaning aof groove & providing sand and hot bitumen fillars and filler metal etc.,including cost of conveyance of all materials, labour,lead and lift charges and all the other incidental charges as per drawing and as per specifications, MORTH specification. (P.178/ I.22.8) | Mtr | 136.90 | 121.90 | Rupees one hundred twenty one and paise ninety only |

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.